



1 DELI/BAKERY FIXTURE PLAN
SCALE: 1/4" = 1'-0"

DELI/BAKERY EQUIPMENT SCHEDULE					
DESCRIPTION	STATUS	SIZE	REQD.	MODEL	SUPPLIER/MANUFACTURER
4A SELF-SERVE REFRIGERATED BAKERY	RELOCATED	----	1	----	----
6 4 DOOR REACH-IN FROZEN BAKERY	NEW	----	1	----	----
12 MULTI-DECK SELF-SERVE COLD DELI	NEW	8'-1"x3'-8"x6'-8"	1	OSDM	HILL PHOENIX
12 MULTI-DECK SELF-SERVE COLD DELI	NEW	12'-1"x3'-8"x6'-8"	1	OSDM	HILL PHOENIX
13 WING BAR	NEW	3'-8" x 5'-2" x 4'-8"	1	MHC3644LFF	ATLANTIC HOT FOOD BARS
21 WINE CHEESE	NEW	12'-1"x2'-6"x6'-10"	1	QC-12R 30	HILL PHOENIX
29 COLD SANDWICH - SERVICE/SELF-SERVE	NEW	4'-1" x 4'-5" x 4'-5"	1	PT-54-4R-RRS	HILL PHOENIX
35A COLD DELI - SERVICE/SELF-SERVE	RELOCATED	----	1	----	----
76 MOBILE HOT FOOD MERCHANDISER	NEW	3'-8" x 3'-10" x 4'-8"	1	MLDH3644	ATLANTIC HOT FOOD BARS
30A SLICER STAND	RELOCATED	----	2	----	----
33A S.S. TABLES	RELOCATED	----	5	----	----
34-4 COMBO S.S. TABLE AND BOAT RACK	NEW	4'-0"x2'-8"x6'-9"	1	ST6R5-3048SSW/INT-MBRB-FL	JOHN BOOS & COMPANY
34-6 COMBO S.S. TABLE AND BOAT RACK	NEW	6'-0"x2'-8"x6'-9"	1	ST6R5-3072SSW/INT-MBRB-FL	JOHN BOOS & COMPANY
34-8 COMBO S.S. TABLE AND BOAT RACK	NEW	8'-0"x2'-8"x6'-9"	1	ST6R5-3096SSW/INT-MBRB-FL	JOHN BOOS & COMPANY
37 BOAT RACK	NEW	6'-0"x1'-8"x2'-0"	1	MBR3620-2SH-FL	JOHN BOOS & COMPANY
41-4 COOLER RACKS	NEW	4'-0"x2'-0"x6'-0"	4	SU10-4824-4-T	CHOICE EQUIPMENT
41-5 COOLER RACKS	NEW	5'-0"x2'-0"x6'-0"	4	SU10-6024-4-T	CHOICE EQUIPMENT
86 SOLID SHELVING	NEW	5'-0"x2'-0"x6'-0"	1	SUS-6024-S	CHOICE EQUIPMENT
45A WALK-IN-COOLER - DELI/BAKERY	EXISTING	----	1	----	----
46A WALK-IN-FREEZER - DELI/BAKERY	EXISTING	----	1	----	----
48 SINGLE RACK OVEN - ELECTRIC	NEW	4'-7"x4'-3"x8'-4"	1	LRO-1E	LBC BAKERY EQUIPMENT
49A FRYER AND FILTER	EXISTING	----	1	----	----
50A BASKET FRYER	EXISTING	----	1	----	----
52A ROTISSERIE W/STAND	EXISTING	----	1	----	----
93A CONVECTION OVEN	EXISTING	----	1	----	----
93 SLICERS - AUTOMATIC	NEW	2'-11"x2'-8"x2'-1"	1	GSP-HD	SIZERBA
53A SLICERS - 2 MANUAL	RELOCATED	----	2	----	----
54A WRAPPING MACHINE	RELOCATED	----	1	----	----
55A BREAD SLICER	RELOCATED	----	1	----	----
56 SCALE w/BUILT-IN PRINTER	NEW	1'-3"x1'-5"x1'-6"	1	HT1HWS-ES	HOBART
57A FLY TRAP	EXISTING	----	2	----	----
68 REFRIGERATED BREADING STATION - 48"	NEW	2'-8" x 3'-10" x 4'-0"	1	9148W	UNIFIED BRANDS
118A CAKE DECORATOR/PRINTER	RELOCATED	----	1	----	----
61A DESK (WALL MOUNTED)	EXISTING	----	1	----	----
60A FILING CABINET	EXISTING	----	1	----	----

DELI/BAKERY GENERAL NOTES:

- THE GENERAL CONTRACTOR IS RESPONSIBLE FOR COMPLIANCE WITH ALL HEALTH DEPARTMENT REQUIREMENTS.
- ACCESSORIES FOR PRESSURE FRYER: A. HEAVY DUTY CASTERS, B. FILTER HOSE.
- PLUMBING CONTRACTOR IS TO INSTALL ALL SINKS AND EYE WASH UNITS.
- THE MECHANICAL CONTRACTOR SHALL PROVIDE AND INSTALL MECHANICAL EQUIPMENT FOR THE DELI/BAKERY AS REQUIRED.
- THE EQUIPMENT LISTED IN THE DELI/BAKERY EQUIPMENT SCHEDULE IS SUPPLIED BY FOOD LION, AND IS SET IN PLACE BY FOOD LION'S REFRIGERATION CONTRACTOR. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL ELECTRICAL, PLUMBING, AND H.V.A.C. EQUIPMENT CONNECTIONS.
- THE GENERAL CONTRACTOR SHALL INSTALL THE BOAT RACKS THAT ARE PROVIDED BY FOOD LION. THE GENERAL CONTRACTOR SHALL COORDINATE THE EXACT LOCATION WITH A FOOD LION CONSTRUCTION SUPERVISOR.
- THE PAPER TOWEL HOLDERS ARE SUPPLIED BY FOOD LION AND INSTALLED BY THE GENERAL CONTRACTOR. INSTALL THE PAPER TOWEL HOLDERS AT 3'-0" ABOVE FINISHED FLOOR.
- MOUNT FLY TRAPS AT 5'-0" ABOVE FINISHED FLOOR IN DELI/BAKERY AND PRODUCE PREP.
- TWO ADDITIONAL 3' DIAMETER DISPLAY TABLES, MODEL No. 1810-1809-1, SHALL BE SUPPLIED IF THE STORE HAS A REFRIGERATED FLORAL DISPLAY.
- THE GENERAL CONTRACTOR SHALL SUPPLY AND INSTALL TWO BROOM HANGERS AND THREE MOP HANGERS IN THE DELI. ALSO SUPPLY AND INSTALL A 12"x24" SHELF IN THE CLOSET AT 6'-0" ABOVE FINISHED FLOOR. COORDINATE LOCATION OF THE SHELF AND HANGERS WITH FOOD LION IF NOT ALREADY INSTALLED.
- THE GENERAL CONTRACTOR SHALL PROVIDE AND INSTALL A SYSTEM (3 ROWS OF 5 CLIPBOARD EACH) FOR HANGING FIFTEEN CLIPBOARDS ABOVE THE DESK IN THE DELI IF NOT ALREADY INSTALLED.